

GOVERNMENT OF GOA
WATER RESOURCES DEPARTMENT
S.D.III., Works Div. XI, QUALITY CONTROL LABORATORY
Gogol - Margao - Goa.

No. WRD / WD XI / SDIII /TECH /WF. 36-Oct-2024 /226 / 2024-25. dated: 06/12/24

Name of the Work: Maintenance and repairs to the branch B2 of WC 6, 7, 8 and 9 of SIP canal and other repairs for the year 2024-25.

Sample Sent by: Assistant Engineer , SD III, WD X, WRD, Quepem- Goa.

Letter No: WRD/ WD X/ SD III/W.F.08/153/2024-25.

Dated:- 2/12/2024

Received on: 2/12/2024

Date of Testing 6/12/2024

REPORT

Sample No.	Type of Sample	Tested for	Result	Permissible value	REMARKS
F. 36/01/2024	Coarse Sand	FM Silt & Clay Grading	2.808 3.00% Zone III	2.3 to 3.1 Upto 5% I to III Zone	
F. 36/02/2024	Aggregate-20 mm	Grading		As per IS-383-1970 (Re-affirmed in 1990)	To get the 20mm graded aggregate nominal size blend 20mm & 12.5 mm metal in 1:1 proportion.
F. 36/03/2024	Aggregate- 12.5 mm	Grading		As per IS-383-1970 (Re-affirmed in 1990)	

Junior Engineer

Assistant Engineer

Copy submitted to

- 1) Assistant Engineer, SD III, WD X, WRD, Quepem- Goa.
- 2) The Executive Engineer, Works Division XI, WRD, Rawanfond- Goa.
- 3) The Executive Engineer, Works Division X, WRD, Pajimol- Sanguem- Goa.
- 4) The Surveyor of Works, Quality Control, C.P.O., Water Resources Dept., Sinchai Bhavan, Alto Porvorim-Goa.
- 5) Office File.